

NOTES:
1. BLANK OFF ALL RETURN AIR
OPENINGS AT LIGHT FIXTURES
WITHIN 15'0" RADIUS OF MAIN
RETURN AIR DUCTS TO SHAFTS.
RETURN AIR OPENINGS AT
EXTERNAL LIGHT FIXTURES
ALSO TO BE BLANKED OFF.
REMAINDER TO BE ACTIVE.

NOTE:
KITCHEN SERVICES NOT TO BE INCLUDED IN BASE BID.
THE 24" DIA EXHAUST DUCT & THE 1 1/2" CONDENSER WATER
SUPPLY & RETURN WILL THEREFORE BE TERMINATED AT THE
CORE WALL. FOR BASE BID, BASE BID SHALL INCLUDE FOR
A BELLMOUTH OPENING TO BE ARRANGED ON EXHAUST DUCT
AT CORE WALL FOR VALVED & CAPPED ENDS AT CONDENSER
WATER PIPES AT CORE WALL, ALSO INCLUDE 100'-0" OF
16" DIA DUCT & 6" DIA FLEXIBLE CONNECTIONS EACH 8'-0"
LONG FOR ADDITIONAL AIR TERMINALS.

A SEPARATE PRICE SHALL BE SUBMITTED FOR THE
FULLY EXTENDED KITCHEN SERVICES INCLUDING ALL
PIPING & DUCTWORK & AIR TERMINALS ETC. AS SHOWN
IN THESE DOCUMENTS.

